

बिहार स्टेट मिल्क को-ऑपरेटिव फेडरेशन लि०,
डुकाई - रांची डेयरी, पोस्ट-एच०ई०सी० सेक्टर-२, धर्वा, रांची - 834004

कॉम्फेड.आरडी.अमि०:

760

निविदा सूचना

दिनांक :

09/11/19

निम्नलिखित कार्यों के लिए वैसे संवेदक जिनका निबंधन बिहार सरकार के भवन निर्माण विभाग/ग्रामीण कार्य विभाग/जल संसाधन विभाग या कॉम्फेड के समुचित श्रेणी में है, से मुहरबन्द निविदाएँ आमंत्रित की जाती हैं। कॉम्फेड को छोड़कर अन्य विभागों में निबंधित संवेदकों को परिमाण विपत्र के क्रय के समय यह साक्ष्य जमा करना होगा कि उनके द्वारा विगत चार वर्षों में नीचे उल्लिखित कार्यों के लागत का जिसके लिए निविदा दे रहे हैं या उससे अधिक का कम से कम दो अलग-अलग समान प्रकृति का (भवन निर्माण का) कार्य अवश्य पूरा किया गया हो। इस साक्ष्य के अभाव में परिमाण विपत्र निर्गत नहीं किया जाएगा।

परिमाण विपत्र अद्योहस्ताक्षरी के कार्यालय से दिनांक 08.04.19 से 12.04.19 के 5.00 बजे संध्या तक क्रय किया जा सकता है अथवा कॉम्फेड के वेब साइट (www.sudha.coop) से डाउनलोड किया जा सकता है। वेबसाइट से डाउनलोड किये गए परिमाण विपत्र का मूल्य डिमाण्ड ड्राफ्ट के रूप में देय होगा जो बिहार स्टेट मिल्क को-ऑपरेटिव फेडरेशन लि०, रांची के नाम से देय होगा। निविदा निबंधित डाक या कुरियर द्वारा भेजे जाने पर ही स्वीकार की जाएगी। निविदा जमा करने की अंतिम तिथि 17.04.19 के 4 बजे अपराह्न तक होगी। प्राप्त निविदाएँ दिनांक 18.04.2019 को 11 बजे पूर्वाह्न में खोली जाएंगी जिसमें निविदादाता या उनके अधिकृत प्रतिनिधि उपस्थित रह सकते हैं। विलम्ब से प्राप्त निविदा के लिए रांची डेयरी जिम्मेवार नहीं होगी। कॉम्फेड के संवेदकों को छोड़कर अन्य संवेदकों को निविदा प्रपत्र के साथ सभी कागजात यथा जी०एस०टी०, पैन निबंधन, भुगतान प्रमाण-पत्र की स्वअभिप्रमाणित प्रति संलग्न करना होगा अन्यथा इसके अभाव में निविदा पर विचार नहीं किया जाएगा। निविदा की तिथि बढ़ाने या रद्द करने का अधिकार अद्योहस्ताक्षरी/रांची डेयरी प्रबंधन को सुरक्षित रहेगा।

क्र० सं०	कार्य का नाम	प्राक्कलित राशि (रु० में)	अग्रघन की राशि (रु० में)	परिमाण विपत्र का (मूल्य रु० में)	कार्य समाप्ति की अवधि
1.	रांची डेयरी में पम्प रूम, पानी टंकी एवं पानी मिटर तथा मुख्य माल्ट डैक के मरम्मत एवं निर्माण का कार्य।	1,95,436.00	4000.00	500.00	02 (दो) माह

मुख्य कार्यपालक
रांची डेयरी, रांची

6

Signature of the Cashier

Signature of Contractor

Chief Executive
Ranchi Dairy, Ranchi

TENDER DOCUMENT

(Strengthening and construction of pump room, water tank and pump tank at Ranchi Dairy.)

Important Dates

Sale of tender document - From 08.04.2019 to 12.04.2019 (up to 5 pm)

Receipt of completed tender- 17.04.2019 (up to 4 p.m.)

Opening of tender - 18.04.2019 at 11 a.m.

Cash Memo No. : Dtd.

Signature of the Cashier

Signature of Contractor

**Chief Executive
Ranchi Dairy, Ranchi**

BOQ FOR THE STRENGTHENING AND CONSTRUCTION OF PUMP ROOM, WATER TANK AND WATER METER & MAN VALVE TANK AT RANCHI DAIRY, RANCHI STATE –JHARKHAND.

THE RATES OF ITEMS ARE BASED ON CURRENT S.O.R. OF SOUTH CHHOTANAGPUR, GOVT. OF JHARKHAND & B.S.R.						
SNo.	SOR Ref No	Description of items	Quantity	Unit	Rate/Unit	Amount
1.	5.10.3	Dismantling R.C.C. work including-do-	2.525	m ³	1435.57	3624.10
2.	5.10.1	Dismantling Pucca brick or lime work including stacking sevvicable materials in countable stacks -do-	0.203	m ³	390.16	79.01
3.	5.10.4	Dismantling Patent stone floor including -do-	0.597	m ³	29.35	17.51
4.	5.10.2	Dismantling plain cement work including -do-	2.033	m ²	688.52	1399.68
5.	5.10.7	Dismantling old plaster and pointing in cement or lime and raking out joints-do-	246.585	m ²	15.46	3812.20
6.	5.10.12	Taking down chaukhats in windows including -do-	1.000	no	99.44	99.44
7.	5.3.2.1	Providing PCC M 200 with nominal mix of (1:1.5:3) in foundation with approved quality of stone metal grade III (50mm to 25mm), size clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position.	4.066	m ³	5829.00	23699.26
8.	5.2.2	Providing designation 75A brick work in C.M (1:4) in foundation and plinth with approved quality of clean coarse sand of F.M. 2 to 2.5 including providing 10mm thick mortar, joints cost of screening materials raking out joints to 15mm depth, curring.	1.215	m ³	4031.90	4898.76
9.	5.2.10	Providing designation 75A brick work in C.M. (1:4) in superstructure with approved quality of clean coarse sand of F.M. 2 to 2.5 including, providing 10mm thick mortar joints, cost of screening materials, raking out joints to 15mm depth curing, taxes -do-	0.270	m ³	4128.29	1114.64

Chief Executive

Ranchi Dairy, Ranchi.

Signature of Contractor

10.	5.3.9.1	Providing R.C.C.M 200(1:1. 5:3) in roof slab with approved quality of stone chips 20mm to 6mm size graded and clean coarse sand of F.M 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position, vibrating, striking,	2.525	m ³	7523.28	18992.52
11.	5.6.7	Providing 25mm thick first class patent stone flooring (1:2:4) with stone chips in two layers, bottom layer 19	27.555	m ²	257.98	7108.64
12.	5.7.16	Providing 25 mm thick water proof cement plaster (1:3) with clean coarse sand of F.M. 1.5 with 5% cico or any other approved water proofing compound including screening, curing with all leads and lifts of water, scaffolding taxes and royalty all complete	22.950	m ²	219.51	5037.75
13.	5.8.26	Providing primer one coat of approved shade and make over new wooden surface including preparing the surface –do-	4.253	m ²	25.96	110.39
14.	5.8.32	Providing two coats of synthetic enamel paints of approved shade and make over new wooden surface-do-	4.253	m ²	161.80	688.05
15.	5.7.6	Providing 6 mm thick cement plaster (1:4) in ceiling with clean coarse sand of F.M. 1.5 including screening, curing with all leads and lifts of water, scaffolding taxes and royalty all complete as per buildings specification and direction of E/I.	22.950	m ²	136.62	3135.43
16.	5.7.1	Providing 12mm thick cement plaster (1:3) with clean coarse sand of F.M 1.5 including screening, curing with all leads and lifts of water, scaffolding taxes and royalty all complete as per building specification and direction of E/I	328.260	m ²	140.52	46127.10

Chief Executive

Ranchi Dairy, Ranchi.

Signature of Contractor

17.	5.7.11	Providing 1.5 mm cement punning including curing-do-	157.210	m ²	43.15	6783.61
18.	5.8.24	Providing two coat of snowcem of approved shade and make over a coat of cement primer on new surface including preparing the plastered surface smooth with sand paper, scaffolding, curing and taxes all complete	198.750	m ²	85.55	17003.06
19.	5.5	Providing Tor steel reinforcement of 8 mm & 10 mm dia rods as per approved design and drawing including carriage of Rods (straight or in coils) to work site, cutting, bending and binding with annealed wire with cost of wire, removal of rust, -do-	0.303	MT		
	5.5.4	8mm	0.212	mt	65841.84	13958.47
	5.5.5 (a)	10mm	0.091	mt	65841.84	5991.60
		Total				163681.23
20.		Add : Carriage			(+) Rs.	9088=03
		GRAND TOTAL				1,72,769=26
					Say	1,72,769=00
Rupees One lakhs seventy one thousands eight hundred thirty five only/-						

Chief Executive

Ranchi Dairy, Ranchi.

Signature of Contractor

**SUMMARY OF COST FOR STRENGTHENING AND CONSTRUCTION OF
PUMP ROOM, WATER TANK AND WATER METER & MAIN VALVE TANK
AT RANCHI DAIRY, RANCHI, DISTT-RANCHI.**

Sl. No.	Description	Page No.	Quantity	Rate	Amount in Rs.
1	PUMP ROOM, WATER TANK AND WATER METER & MAIN VALVE TANK				1,72,769.00
2	Add GST			12%	20,732.28
	Total				1,93,501.28
3	Labour cess			1%	1935.01
	Total				1,95,436.29
	Say				1,95,436.00
Rs. One lack ninety five thousand four hundred thirty six only.					

I am ready to do the work.

1. On estimated cost :-
2. Above estimated cost :-
3. Below estimated cost :-

Chief Executive

Ranchi Dairy, Ranchi.

Signature of Contractor

BIHAR STATE MILK CO-OPRATIVE FEDERATION LTD.,
Unit – Ranchi Dairy, HEC Sector II, Dhurwa, Ranchi - 834004

1. Sealed tender on prescribed B.O.Q to be eventually drawn in P.W.D. Form- F2 will be received from the Registered Contractors of Building Construction Dept Govt. of Bihar/ RWD/ Water Resources Department, Govt. of Bihar & Comfed up to **4 PM on 17.04.2019** by the Ranchi Dairy, **Bihar State Milk Co-operative Federation, Ltd.** for the work of **Strengthening and construction of pump room, water tank and pump tank at Ranchi Dairy** and will be opened in the presence of the tenderers or their authorized agents on **18.04.2019 at 11 AM.**
2. Tenderes should complete the work within **Two months** commencing from the date of receipt of written order to commence the work.
3. Tenderers are requested to deposit earnest money at the rate of Rs. 100/- (One hundred) for every Rs. 5000/- or part on the amount of estimate. The earnest money is to be deposited in shape on NSC duly pledged to the **Bihar State Milk Co-operative Federation Ltd.** Bank Draft in-favour of the **Bihar State Milk Co-operative Federation Ltd. payable at Ranchi.** Will also be accepted.
4. The plan, elevation and specification for the work can be seen at the officer of the Manager (Engg.) COMFED and I/c Engg., I/c Plant Ranchi Dairy during the working hour and day.
5. All other information can be obtained on application from the undersigned.
6. The authority reserves the right to reject any or all the tender received without assigning any reason there-of.
7. The earnest money of the successful tenderer which accompanies the tender will be forfeited in case he declines to sign. The agreement/contractor to deposit balance security within ten days of being called upon to do so. after the acceptance of his tender.
8. The amount of estimate is Rs. **1,95,436.00/-.**
9. The rates should be inclusive of all materials. The tenderer should also indicate the rebate they will allow if levy cement @ Rs. **Nil** per bag either in full or part is arranged for the work.
10. The bill of quantity for the work can be had as per tender notice from the office of the Ranchi Dairy during working hours and days on payment of Rs. **500.00** (non refundable).
11. Up- date I.T.C. & other documents as per tender notice should be attached with tender otherwise it is liable to be rejected.
12. The contractor must note his registration no./category of Registration and office in which registered distinctly.
13. The tenderer should furnish his full postal address so that any latter at his given postal address will be deemed to have been received by him.

Signature of Contractor

Chief Executive
Ranchi Dairy, Ranchi

PECIAL CONDITION FOR THE WORK

_____ Nil _____

_____ Nil _____

1. No claim will be entertained due to idle labour and/any or and other cause.
2. levy cement if supplied by the Federation will be at the rate noted below :-
 - a. Cement:- _____ N.A _____
 - b. Place of delivery:- _____ N.A _____
3. The contractor will have to provide huts for the labourers at his own cost and will have to observe all labour rules including observance of the minimum labour waged.
4. After completion of work, the site of the work will have to be cleared off from all rubbish and un-used materials for which no extra payment will be made.
5. Time of completion of the work is Two months from the date of issue of work order. However the contractor may quote his own line of completion.
6. The contractor employing motor vehicles should follow rules with regard to motor vehicles.
7. For excess consumption of the Federation materials over the actual requirement, recovery will be made at panel rate i.e. double of issue rate.
8. Only kiln burnt bricks will have to be used by the contractor in construction of work.
9. The contractor will be liable to pay compensation under the work-man's Act for accident or loss of life, if any.
10. The contractor will have to maintain site order book on the site of work exhibitable to inspecting officers any time on demand.
11. All works shall be carried out in workmanship like manner and as per standard specification of the Federation.
12. The authority reserves the right on distribution of work among several contractors.
13. Two percent (2%) Income Tax, 5% Security and Sales Tax/GST (Good Service Taxes) as per rule will be deducted from all payments (Gross amount).

Signature of Contractor

Chief Executive
Ranchi Dairy, Ranchi

14. The tenderers are presumed to have inspected the site and acquainted himself with the local condition of the work and no claim due to ignorance these conditions and also site conditions will be entertained.
15. No claim will be entertained for fluctuation of the rates of labour/materials and carriage at any stage of work under progress.
16. Items of work beyond agreement shall not be executed by the contractor, if this becomes a necessity, written order of Engineer In-charge should be obtained before taking up such works. Such items shall ordinarily be paid at schedule of rate. However, Contractor may prefer a claim before taking up such works and await decision of rates by the competent authority.
17. Quantity of work may increases or decrease in accordance with the order of E/I.
18. Contractor will assist supervision of work, measurement and verification of bills by the officers of the Federation and will mend good any items damaged in course of inspection, measurement and verification of work.
19. Site shall be cleared and kept clean by the contractor at their own cost during completion of work.
20. Foundation trench shall have to be kept dry during the execution of work & de-watering can be ordered by the E/I if necessary.
21. Only LAFARGE, A.C.C PRISM, L & T & GRASIM cement will be used.

Signature of Contractor

Chief Executive
Ranchi Dairy, Ranchi